

1 Elmhurst Avenue

Address	Area Details	Treatment			Area (Sq Yd)	
		Slab Jack	Replace	Grind		New
702-714 Elmhurst	Install approximately 215 SY of 4" wide 4" thick sidewalk				X	215
704 Elmhurst	Remove and replace approximately 15 SY of 6" thick sidewalk and apron		X			15
706 Elmhurst	Remove and replace approximately 16 SY of 6" thick sidewalk and apron		X			16
708 Elmhurst	Remove and replace approximately 14 SY of 6" thick sidewalk and apron		X			14
714 Elmhurst	Install approximately 6 SY of ADA ramp at SE corner of Elmhurst and Bond				X	6
702 Elmhurst	Install approximately 12 SY of ADA ramp at SE and NE corners of Elmhurst and Grove				X	12
758 - 1014 Elmhurst	Install approximately 173 SY of 4" wide 4" thick sidewalk				X	173
758 - 1014 Elmhurst	Remove and replace approximately 100 SY of 6" thick sidewalk and apron		X			100
303 Elmhurst	Install approximately 11 SY of 4" wide 4" thick sidewalk		X			11
307 Elmhurst	Install approximately 7 SY of 4" wide 4" thick sidewalk		X			7
304 Elmhurst	Install approximately 7 SY of 4" wide 4" thick sidewalk		X			7
						576

2 Beech Street

Address	Area Details	Treatment			Area (Sq Yd)	
		Slab Jack	Replace	Grind		New
306 Beech	Remove and replace approximately 17 SY of 4" wide 4" thick sidewalk		X			17
306 Beech	Remove and replace approximately 60 SY of 6" thick sidewalk and apron		X			60
508 Morgan	Remove and replace approximately 41 SY of 4" wide 4" thick sidewalk		X			41
501 Beech	Remove and replace approximately 37 SY of 4" wide 4" thick sidewalk		X			37
						118

3 Morgan Blvd

Address	Area Details	Treatment			Area (Sq Yd)	
		Slab Jack	Replace	Grind		New
506 Morgan	Remove and replace approximately 22 SY of 4" wide 4" thick sidewalk		X			22
506 Morgan	Remove and replace approximately 34 SY of 6" thick sidewalk and apron		X			34
						56

4 Elm Street

Address	Area Details	Treatment			Area (Sq Yd)	
		Slab Jack	Replace	Grind		New
509 Elm	Remove and replace approximately 20 SY of 4" wide 4" thick sidewalk		X			20
						20

5 Franklin Street

Address	Area Details	Treatment			Area (Sq Yd)	
		Slab Jack	Replace	Grind		New
1101 Franklin	Remove and replace approximately 7 SY of 4" wide 4" thick sidewalk		X			7
1103 Franklin	Remove and replace approximately 20 SY of 6" thick sidewalk and apron		X			20
1103 Franklin	Remove and replace approximately 12 SY of 4" wide 4" thick sidewalk		X			12
1105 Franklin	Remove and replace approximately 24 SY of 4" wide 4" thick sidewalk		X			24
1105 Franklin	Remove and replace approximately 16 SY of 6" thick sidewalk and apron		X			16
1107 Franklin	Remove and replace approximately 19 SY of 4" wide 4" thick sidewalk		X			19
1107 Franklin	Remove and replace approximately 14 SY of 6" thick sidewalk and apron		X			14
1108 Franklin	Remove and replace approximately 12 SY of 6" thick sidewalk and apron		X			12
1110 Franklin	Remove and replace approximately 4 SY of 4" wide 4" thick sidewalk		X			4
1107 Franklin	Remove and replace approximately 12 SY of 6" thick sidewalk and apron		X			12
						140

6 Stanley Street

Address	Area Details	Treatment			Area (Sq Yd)
		Slab Jack	Replace	Grind	
208 Stanley	Remove and replace approximately 22 SY of 4" wide 4" thick sidewalk		X		22
208 Stanley	Remove and replace approximately 12 SY of 6" thick sidewalk and apron		X		12
300 Stanley	Remove and replace approximately 15 SY of 6" thick sidewalk and apron		X		15
					49

7 Northview Drive

Address	Area Details	Treatment			Area (Sq Yd)
		Slab Jack	Replace	Grind	
161 Northview	Remove and replace approximately 5 SY of 4" wide 4" thick sidewalk		X		5
					5

8 Napoleon Street

Address	Area Details	Treatment			Area (Sq Yd)
		Slab Jack	Replace	Grind	
1614 Napoleon	Remove and replace approximately 36 SY of 4" wide 4" thick sidewalk		X		36
1614 Napoleon	Remove and replace approximately 10 SY of ADA ramp at SE and NE corners of Napoleon and Northview		X		10
1614 Napoleon	Remove and replace approximately 15LF curb and gutter at SE corner of Napoleon and Northview		X		15
1310 Napoleon	Remove and replace approximately 10 SY of 4" wide 4" thick sidewalk		X		10
					71

9 Harrison Blvd

Address	Area Details	Treatment			Area (Sq Yd)
		Slab Jack	Replace	Grind	
162 Harrison	Remove and replace approximately 8 SY of 4" wide 4" thick sidewalk		X		8
158 Harrison	Remove and replace approximately 10 SY of 4" wide 4" thick sidewalk		X		10
158 Harrison	Remove and replace approximately 29 SY of 6" thick sidewalk and apron		X		29
154 Harrison	Remove and replace approximately 14 SY of 4" wide 4" thick sidewalk		X		14
1112 Campbell St	Remove and replace approximately 32 SY of 4" wide 4" thick sidewalk		X		32
1112 Campbell St	Remove and replace approximately 24 SY of 6" thick sidewalk and apron		X		24
					117

10 Wood Street

Address	Area Details	Treatment			Area (Sq Yd)
		Slab Jack	Replace	Grind	
1002 Wood St - 213 Roosevelt Rd	Remove and replace approximately 195 SY of 5" wide 4" thick sidewalk		X		195
1002 Wood St - 213 Roosevelt Rd	Remove and replace approximately 120 SY of 6" thick sidewalk and apron		X		120
					315

11 Tuckahoe Park Drive

Address	Area Details	Treatment			Area (Sq Yd)
		Slab Jack	Replace	Grind	
1406 Tuckahoe	Remove and replace approximately 5 SY of 4" wide 4" thick sidewalk		X		5
1405 Tuckahoe	Remove and replace approximately 5 SY of 4" wide 4" thick sidewalk		X		5
1308 Tuckahoe	Remove and replace approximately 8 SY of 4" wide 4" thick sidewalk		X		8
1306 Tuckahoe	Remove and replace approximately 5 SY of 4" wide 4" thick sidewalk		X		5
1711 Tuckahoe	Remove and replace approximately 10 SY of 4" wide 4" thick sidewalk		X		10
1801 Tuckahoe	Remove and replace approximately 10 SY of 4" wide 4" thick sidewalk		X		10
					43

12 Chamblee Drive

Treatment

Address	Area Details	Slab Jack	Replace	Grind	New	Area (Sq Yd)
2003 Chamblee	Remove and replace approximately 10 SY of 4" wide 4" thick sidewalk		X			10
						10

13 Cedar Court

Address	Area Details	Treatment				Area (Sq Yd)
		Slab Jack	Replace	Grind	New	
701 - 710 Cedar Ct	Remove and replace approximately 230 SY of 5" wide 4" thick sidewalk		X			230
701 - 710 Cedar Ct	Remove and replace approximately 164 SY of 6" thick sidewalk and apron		X			64
						294

14 College Avenue

Address	Area Details	Treatment				Area (Sq Yd)
		Slab Jack	Replace	Grind	New	
505 College Ave	Remove and replace approximately 25 SY of 6" thick sidewalk and apron		X			25
						25

15 Saddlebrook Crossing

Address	Area Details	Treatment				Area (Sq Yd)
		Slab Jack	Replace	Grind	New	
3301 Saddlebrook	Remove and replace approximately 10 SY of 5" wide 4" thick sidewalk		X			10
						10

16 Franklin Street

Address	Area Details	Treatment				Area (Sq Yd)
		Slab Jack	Replace	Grind	New	
510 Franklin	Remove and replace approximately 30 SY of 4" wide 4" thick sidewalk		X			30
601 - 603 Franklin	Remove and replace approximately 25 SY of 4" wide 4" thick sidewalk		X			25
512 Franklin	Remove and replace approximately 15 SY of 4" wide 4" thick sidewalk		X			15
						70

17 Naples Drive

Address	Area Details	Treatment				Area (Sq Yd)
		Slab Jack	Replace	Grind	New	
2351 Naples	Remove and replace approximately 10 SY of 5" wide 4" thick sidewalk		X			10
						10

18 Pineview Lane

Address	Area Details	Treatment				Area (Sq Yd)
		Slab Jack	Replace	Grind	New	
3904 Campbell (Pineview side)	Install approximately 17 SY of 5" wide 4" thick sidewalk				X	17
						17

19 Sturdy Road

Address	Area Details	Treatment				Area (Sq Yd)
		Slab Jack	Replace	Grind	New	
2002 Sturdy Road	Remove and replace approximately 75 LF curb and gutter at SE corner of Napoleon and Northview		X			75
						75

20 Blue River Road

Address	Area Details	Treatment				Area (Sq Yd)
		Slab Jack	Replace	Grind	New	

